



LIFT STD SPECIFICATION

- Load capacity - 250kg
- Drive system - Screw & Nut
- Speed - 0.04 m/s
- Maximum number of stops - 2
- Maximum Travel - 1m
- Pit - Not required (0mm)
- Power - 230V-mono AC – 50Hz 10A
- Motor - 0.6 kW
- Cabin COP - Full height Vertical
- Platform Controls - Constant Pressure
- Landing Controls - Constant Pressure
- Flooring - Aluminium Checker plate
- Carriage Finish - RAL 7040 Grey Papyrus
- Gate Type - Swing
- Gate Finish - RAL 7040 Grey Papyrus
- Communication - N/A
- Handrail - Included
- Auto Folding ramp - Included

Options

- Stainless Steel Finish to all steelwork
- Automatic Gate
- Glass Carriage Walls
- Glass Gate
- Radio frequency landing controls
- Remote post for landing controls
- Alternative RAL Finishes to carriage & gate



PREMIER LIFTS
www.lifts.ie

Premier Lifts, Glean Glas House,
Tuamgraney, Co. Clare, Ireland.
Tel: 061 922 903 Email: info@lifts.ie
Fax: 061 922 904 Web: www.lifts.ie

VPL200 – 1200mm x 850mm
Through Entry/Exit

DWG NO - 0061

REV - A

SCALE

DATE

DRAWN

NTS

10/11/2017

APG

NOTE THIS DRAWING IS FOR GUIDANCE ONLY AND MUST NOT BE USED AS A PROPER WORKING DRAWING. FOR ENQUIRIES ABOUT THE LIFT PLEASE CONTACT 061 922 903



Premier Lifts, Glean Glas House,
Tuamgraney, Co. Clare, Ireland.
Tel: 061 922 903 Email: info@lifts.ie
Fax: 061 922 904 Web: www.lifts.ie

VPL200 – 1200mm x 850mm
Through Entry/Exit

DWG NO - 0061

REV - A

SCALE
NTS

DATE
11/10/2011

DRAWN
APG